

ZESTAWIENIE STALI
PRZEBUDOWA POMIESZCZEŃ AWF W POZNANIU
Rys. 7/Kw

nie obejmuje dodatku na spoiny

ELEMENTY 22 i 23 w LABORATORIUM

Poz.	Profil	Gat.stali	Dlugosc mm	Ciezar1m kG	Ciezar 1e		Ciezar razem kG	Ogolem
					losc	szt.		
1	Bl.8x229	304	1800	14,38	25,9	2,0	51,8	
2	Bl.8x91	304	1800	5,7	10,3	4,0	41,0	
3	Bl.6x164	304	1800	7,72	13,9	2,0	27,8	
4	Bl.10x200	S235	229	15,7	3,6	8,0	28,8	
5	RK80x6	S235	608	13,6	8,3	4,0	33,1	
6	RK80x6	S235	590	13,6	8,0	2,0	16,0	
7	M20	S235	676	2,5	1,7	1,0	1,7	
8	Bl.3x67	S235	67	1,6	0,1	12,0	1,3	
9	Bl.10x100	S235	160	7,85	1,3	1,0	1,3	

202,7	1	202,72
-------	---	--------